

# **Interstate 405 Improvement Project**









### **Background**





### **Project Description**



The project adds 1 general purpose and 1 express lane. The express lane, when combined with the existing carpool lane, creates the I-405 Express Lanes, a two-lane each direction express facility similar to the 91 Express Lanes.



# **Overcrossing Replacements**





### **Follow Up Items**

- ❖ Focused meeting with Subcommittee on October 21, 2015
- Follow Up Items:
  - Current project design features
  - Combined pedestrian/bike facility
  - Bicycle/pedestrian signage and striping
  - Stop sign at ramp crossing




## **Current Project Design Features**

Description	Existing Condition	Improvement
Free right turns at freeway ramps	25 locations	Project will remove 19 free right turns at ramps
Missing sidewalks on freeway bridge overcrossing	18 locations	Project will provide sidewalks at 14 locations



### **Combined Pedestrian/Bike Facility**

- Revised design to combine pedestrian and bike facility at various locations
- Eastbound Talbert Ave at Southbound 405 entrance ramp
- Eastbound Edinger Ave at Southbound 405 entrance ramp
- Eastbound Bolsa Ave at Southbound 405 ramps
- Eastbound Westminster Blvd at Southbound 405 ramps





#### Bicycle/Pedestrian Signage and Striping

- Addition of W11-1 sign at shared right through lane adjacent to an exclusive right turn lane
- Addition of W11-15 sign at off-ramp not controlled by traffic signals
- Addition of Continental High Visibility Crosswalk Markings (NB and SB off ramps to Bolsa)
- Additional signage will be evaluated per CAMUTCD\* during final design
- Detailed sign plan to be developed during final design







W11-15

Continental crosswalk marking

<sup>\*</sup> California Manual of Uniform Traffic Control Devices



### **Stop Sign at Ramp Crossing**

- Addition of stop sign along "jug handle" design for bike/pedestrian traffic at ramp crossings
- All ramps and crosswalks will be lighted
- Detailed sign plan to be developed during final design





## **Project Schedule**

Description

**Current Schedule** 

Develop Draft Toll Policy and T&R Study	Late 2015/Early 2016
Shortlist DB Teams and Issue DB Draft RFP	November 2015
Issue DB RFP	April 2016
DB Award	December 2016
DB Notice to Proceed	February 2017
Design and Construction	2017 to 2022